Bruhath Benglauru Mahangara Palike, Dasarhalli Zone
Office of the Executive Engineer, Dasarhalli Division.
Schedule - B

Name of the Work : Improvements to roads CC Drain and Covering Slab at Coconut Garden roads and Krishnegowda layout and Surrounding area in Ward no. 15.

Sl No	Item Name	Unit	Quantity	Sanctioned Rate	
				In Figures (Rs)	In Words (Rs)
1	Earthwork excavation by manual means for roads, drains and similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after braking of clods complete as per specifications.	Cum	981.42	207.60	Rupees Two Hundred and Seven and Sixty Paisa Only
2	Providing and Laying plain cement concrete M10 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @ 0.84cum and fine aggregates @ 0.56cum in foundation mechanically mixed placed in foundation and compacted by vibration including curing for 14 days complete as per specifications.	Cum	229.62	5421.90	Rupees Five Thousand Four Hundred and Twenty One and Ninety Paisa Only
3	Providing and Laying plain reinforced cement concrete for side drains using m20 nominul mix concrete with OPC cement 300kgs. With 20mm and down size ganite metal course aggregates @0.69cum and fine aggregates @0.43cum machine mixed, well compacted for walls and bottom inclucing centring, shuttring, cost of materails, HOM of machinaries. Complete Excluding cost of steel asper MORTH Specification.	Cum	326.12	7070.20	Rupees Seven Thousand and Seventy and Twenty Paisa Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Sl No	Item Name	Unit	Quantity	Sanctioned Rate	
				In Figures (Rs)	In Words (Rs)
4	Crushing of stone boulders of 150mm size in an integrated stone crushing unit of 200 tonnes per hour capacity comprising of primary and secondary crushing units, belt conveyor and vibrating screens to obrain stone aggregates of 40mm nominal size complete as per specifications.	Cum	47.57	760.02	Rupees Seven Hundred and Sixty and Two Paisa Only
5	Supplying, fitting and placig TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specifications.	Tonne	18.40	72326.98	Rupees Seventy Two Thousand Three Hundred and Twenty Six and Ninety Eight Paisa Only
6	Providing and laying reinforced cement precast slabs of mix CC 1:11/2:3 using 20mm and down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways and complete as per specifications.	Sqm	1272.33	2208.00	Rupees Two Thousand and Two Hundrad and Eight Only
7	Cement concrete pavement. Constuction of un-reinforced plain cement concrete pavement, thickness as per desihn, over a prepared sub base with OPC cement or any other type as per clause 105 Including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screitudinal joints, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per drawing complete as per specifications. M 30 (at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.43cum) as per Specifications	Cum	96.35	5210.96	Rupees Five Thousand and Two Hundrad and Ten and Ninety Six Paisa Only

EXECUTIVE ENGINEER-1
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Dasarahalli Division